

Secure Environment Commissioning of Wallgate Sanitaryware & Controls

General Requirements:

- 14 days' notice required before commissioning commences, sufficient time must be allowed for completion of the works before project handover, contact Wallgate to be advised of expected duration.
- Pre-commissioning review/meeting with appointed Commissioning Manager, to confirm commissioning requirements.
- All areas to be commissioned must be accessible and no fire seal should be used which prevents access.

Commissioning Service Includes*:

- Confirm that the installation is complete as per Wallgate installation instructions, and the system is ready for commissioning.
- Test for correct operation of installed products, including all connections to/from the electronic controller.
- Check control unit settings & reset to customers' requirements.
- Test/balance WC flush, and functional operation of all sanitaryware and controls (including lighting & power control, if applicable).
- On-site demonstration and system handover with the client.
- Leave in full working order, ready for use.
- Commissioning Report & Certificate will be supplied.

* Please note the above service does not include:

- Any works associated with physical installation or replacement of new products.
- The making of any final connections to mains services (e.g. power, water, waste, etc.).
- Rectification of any defects associated with installation.
- Application of mastic sealant.
- Thermostatic mixer valve (TMV) commissioning.
- Removal and/or replacement of fire stop or any associated costs.

